

R

Form CP-3

Rev. 6-1-68

KANSAS

RECEIVED

STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

AUG 11 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 -135-30043.0001 (of this well)

Operator's Full Name Cities Service Oil Co.

Complete Address 700 Sutton Place, 209 E. William, Wichita, Kansas

Lease Name Mc Junkin "A" Well No. 2 (SWD)

Location SW SW Sec. 10 Twp. 20 Rge. (E) (W) 21

County Ness Total Depth 4447'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 1:30 P Day 9 Month 8 Year 1976

The above well was plugged as follows:

Total Depth 4447' 8 5/8 csg set 504' cwc 300 sk.

4 1/2 csg set 4447' cw 650 sk cem. Top of cem. A/1950'.

4 1/2 csg PBDT 3805' with top perf. (3618'-3634') No pipe recovered.

Tbg set at 1686' -Hallib. Cem. Co. mixed & pumped 20 sk gel & water W/300 lbs hulls-
displaced 70 sk "Hallib. Light" cem.

Pulled tbg to 600' -circ 130 sk "Hallib. Light" to surface -filling annulus & 4 1/2 csg.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 8/12/76

INV. NO. 3623-W

Cities Service will
file "Well Plgd APP"
by Bob Hallom

Lee

15.135.30043.0001