

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Corporation

Complete Address: P. O. Box 1070 Great Bend, Kansas 67530

Lease Name Whipple - Cole Well No. 1

Location NW SE Sec. 19 Twp. 20 Rge. (E) (W) 21

County Ness Total Depth 4370

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 1P Day 12 Month 11 Year 1969

The Above well was plugged as follows:

Total Depth 4370' 8 5/8 csg set at 516' cwc 300 sk.

5 1/2 csg set at 4354' cw 225 sk cmt.

5 1/2 csg PBTD 4350' with top perf. (4336)

Filled 5 1/2 csg W/sd (4300-4350) Dumped 5 sk cmt W/dump bailer. (4260-4300)

Cutoff and recovered 2300' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/2 sk hulls, plug and 120 sk

50-50 poz cmt W/6% total gel. Max. pres. 1000 lbs. SI pres. 750 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Murray
Well Plugging Supervisor

INVOICED

DATE 11/14/69

INV. NO. 839-W