

15.135.30209.0000

Form CP-3
Rev. 6-26-62

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION

JUN 30 1966

CONSERVATION DIV.
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name O. A. Sutton

Complete Address: 407 Insurance Bldg. Wichita, Kansas

Lease Name Lewis Well No. 2

Location 125 Ft. S of C NW NE Sec. 26 Twp. 20 Rge. 21 (E) (W)X

County Ness Total Depth 4477

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drlg. Co.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 10:30 A Day 29 Month 6 Year 1966

The Above well was plugged as follows:

RTD 4477 8 5/8 set at 350 Ft. cw 250 sax cement cir.

Gunned pits, circulated heavy mud, set cementing plug at 540 Ft. and

displaced 25 sc cement thru drill pipe. Heavy mud to 350 Ft. set cementing

plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40 Ft. set

cementing plug, 1/2 sc hulls and 10 sc cement to base of celler. Plugged

rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

6/30/66
3488-W

Signed: Leo Messerly
Well Plugging Supervisor