



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Merckle of Lauck Drlg. has this

date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company

Complete Address: 301 S. Broadway Wichita, Ks.

Lease Name: Rowland Well No. 2

Location: C NW SW Sec. 24 Twp. 20 Rge. 21 (E)(W) X

County: Ness Total Depth 4440' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent