



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 1 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Lacy of Beardmore Drlg Co. has this

date requested permission to plug the following described well:

Mr. Lacy guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drlg. Co.

Complete Address: 700 one-Twenty Bldg. Wichita, Ks.

Lease Name: Mauch Well No. 1

Location: SW SE Sec. 16 Twp. 20 Rge. (E)(W) 23

County: Ness Total Depth 4456 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Lacy was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 430' set cementing plug and

displace 50 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

Leo J. Muesel
 Conservation Division Agent