

State of Kansas



15.135.30232.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Roberts of Strata Drlg. Co. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: R. V. Lehner

Complete Address: Box 398 Ness City, Kansas

Lease Name: Rollins Well No. 3

Location: C SW SE Sec. 13 Twp. 20 Rge. 24 (E)(W) X

County Ness Total Depth 4415 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600 Ft.
and displace 30 sc cement thru drill pipe. Heavy mud to 280 Ft. set
cementing plug and displace 20 sc cement thru drill pipe. Heavy mud
to 40 Ft. set cementing plug, 1/3 sc hulls and 10 sc cement to base
of celler. Plug rat and mouse hole with 5 sc cement.

Very truly yours,

Leo Massey
Conservation Division Agent