

State of Kansas



15.135.21581.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1979

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of Pioneer Drlg. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Liberty Enterprises, Inc.

Complete Address: 308 W. Mill, P-Ville, Ks.

Lease Name: McCreight "A" Well No. 1

Location: C NE SE Sec. 1 Twp. 20 Rge. (E)(W) 23

County: Ness Total Depth 4425' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill
pipe. Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent