



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 30 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cecil Burton of Pickrell Drilling Company has this date requested permission to plug the following described well:

Mr. Pickrell Drlg. Company guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 4th. Nat'l. Bk. Bldg., Wichita, Kansas 67202

Lease Name: Yount "B" Well No. # 1

Location: C SE SW Sec. 8 Twp. 20 Rge. 21 (E)(W)W

County: Ness Total Depth 4453 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Russ Sullivan was instructed to plug the well as follows:

8 5/8" 267' Cwc, 5 1/2" 4448'.

Sanded hole back to 4430' & dumped 5 sax cement with dump bailer.

Pulled pipe, Squeezed well with 10 sax mud & 2 sax hulls, & 130 sax cement with Globe Cementing Company's pump truck, cementing from

450' to base of cellar.

Very truly yours,

Don Sullivan
 Conservation Division Agent