

State of Kansas



15.135.20054.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Merckle of D. R. Lauck Oil Co. has this

date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company

Complete Address: 301 S. Broadway Wichita, Kansas

Lease Name: Shank Well No. 1

Location: C SE NW Sec. 11 Twp. 20 Rge. 21 (E)(W) X

County Ness Total Depth 4525 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 620' and displace

65 sc cement thru drill pipe. Heavy mud to 40' set cementing plug and

1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with

2 sc cement. Cementing material 50-50 poz cem. with 6% gel.

Very truly yours,

Rio F. Massey
Conservation Division Agent