



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 22 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Leben Drlg. has this  
 date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Brandt - Clark

Complete Address: 737 First Nat'l Bank Bldg., Wichita, Ks.

Lease Name: Kramer Well No. 1

Location: C SE NW Sec. 10 Twp. 20 Rge. 21 (E)(W) X

County: Ness Total Depth 4462 Oil Well       

Gas Well        Input Well        SWD Well        D & A XX Lost Hole       

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
50 sc cement thru drill pipe. Heavy mud to 480' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo J. Mussey  
 Conservation Division Agent