

State of Kansas



15.135.30238.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Burton of Pickrell Drlg. Co. has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth Nat'l Bk. Bldg., Wichita, Kansas

Lease Name: Wittman Well No. 2

Location: C SE NE Sec. 19 Twp. 20 Rge. 21 (E)(W) X

County Ness Total Depth 4500 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540 Ft and  
displace 25 sc cement thru drill pipe. Heavy mud to 250 Ft. set cementing  
plug and displace 20 sc cement thru drill pipe. Heavy mud to 40 Ft. set  
cementing plug, 1/3 sc hulls and 10 sc cement to base of celler.  
Plug rat hole with 2 sc cement.

Very truly yours,

Rico Messing  
Conservation Division Agent