

State of Kansas



15.135.30209.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Musgrove of Hellae Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 407 Insurance Bldg. Wichita, Kansas

Lease Name: Lewis Well No. 2

Location: 125,S of C NW NE Sec. 26 Twp. 20 Rge. 21 (E)(W) X

County Ness Total Depth 4477 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540 Ft. and
displace 25 sax cement thru drill pipe. Heavy mud to 350 Ft. set
cementing plug and displace 20 sc cement thru drill pipe. Heavy
mud to 40 Ft. set cementing plug, 1/2 sc hulls and 10 sc cement
to base of celler. Plug rat hole with 2 sax cement.

Very truly yours,

Leo Massey
Conservation Division Agent