

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20657-00-00
Spot: SE Sec/Twnshp/Rge: 2-23S-38W
1345 feet from S Section Line, 1300 feet from E Section Line
Lease Name: DANNEBOHM Well #: 2
County: KEARNY Total Vertical Depth: 3020 feet

Operator License No.: 6067
Op Name: PRAIRIE ENERGY LC
Address: 1240 GLENBROOK DR
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2840		
PROD	5.5	3019	0	
SURF	8.625	324		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2017 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 2840' WITH 2 SX CMT. PLUG AT 2370' WITH 15 SX GEL & 50 SX CMT. PLUG AT 1050' WITH 80 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT OR SQUEEZE PERFS WITH HULLS & 70 SX CMT TO COVER ANHYDRITE TOO. USE GEL ON 1050' PLUG IF THIS ROUTE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2017 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2840'. RAN CBL FROM 2830' TO 35'. HAVE CMT FROM 2830' TO 125'. RUN TBG TO 2834' & SPOT 70 SX CMT UP TO 2100' TO COVER THE ANHYDRITE. CIRCULATE CMT FROM 1117' TO 0' WITH 120 SX CMT. TOP OFF WITH 10 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2886	2964		


INVOICED
JAN 10 2018

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICAN SERVICES.


Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
NOV 21 2017
KCC DODGE CITY 

SR