

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22110-00-00
Spot: W2SWNENE Sec/Twnshp/Rge: 2-13S-31W
990 feet from N Section Line, 1064 feet from E Section Line
Lease Name: FERN OTTLEY Well #: 1
County: GOVE Total Vertical Depth: 4625 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4625		180 SX
SURF	8.625	212		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2017 9:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: BRAD HUTCHINSON Company: PROSPECT OIL & GAS CORP DBA Phone: (785) 483-6266

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/400 # hulls.
8 5/8" surface casing set at 212' w/150 sx cement.
5 1/2" production casing set at 4625' w/180 sx cement.
Stage collar set at 2366' w/180 sx cement.
TD 4625'.
Perforations: 4540' - 4544' and 4573' - 4575', Johnson

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2017 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4494' and pumped 1200 # gel followed by 100 sx cement w/400 # hulls. Pulled tubing to 2411' and pumped 100 sx cement. Pulled tubing to 1400' and pumped 150 sx cement. Circulated cement to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 25 sx cement. Connected to 8 5/8" surface casing and pumped 5 sx cement. Pressured to 300 psi.

GPS: 38.95815N -100.72644W

Perfs:

INVOICED
JAN 10 2018

Remarks: ULTIMATE WELL SERVICE RIG AND QUALITY OILWELL CEMENTING TICKET # 568

Plugged through: TBG

District: 04

Received Signed Darrel Dipman
KANSAS CORPORATION COMMISSION (TECHNICIAN) CM

DEC 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

DEC 12 2017