

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-153-20819-00-00  
Spot: W2W2NW Sec/Twnshp/Rge: 29-5S-36W  
3960 feet from S Section Line, 330 feet from W Section Line  
Lease Name: BRINEY TRUST B Well #: 2  
County: RAWLINS Total Vertical Depth: 4740 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4736		140 SX
SURF	8.625	200		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2017 10:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Well was producing under a packer with perforations at 4532' - 4534' and a tension packer set at 4400'. Casing leaks from 2875' - 2925'. No record of top stage cement.  
Unable to pull packer at 4400'. Ran free point and backed tubing off at 3760'. Decided to plug and abandon.  
Ordered 450 sx 60/40 pozmix 4% gel cement w/1000 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/11/2017 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 2205'. Ran tubing to 3730' and pumped 20 sx cement with no hulls followed by 60 sx cement w/200 # hulls. Pulled tubing to 3400' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2400' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 100 sx cement w/300 # hulls. Cement circulated. PTOH. Topped off casing with 15 sx cement. Hooked up to backside and pumped 10 sx cement. Blew a hole in the nipple on backside. Surface full of cement.

Perfs:

Top	Bot	Thru	Comments
4532	4534		

INVOICED  
JAN 10 2018

Remarks: GLOBAL CEMENT TICKET # 3207

Plugged through: TBG

District: 04

Signed



Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

cm

DEC 20 2017

CONSERVATION DIVISION  
WICHITA, KS

DEC 13 2017