

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-21951-00-00  
Spot: SESWNWSW Sec/Twnshp/Rge: 7-18S-6W  
1635 feet from S Section Line, 4708 feet from E Section Line  
Lease Name: WILLIAMS Well #: 1-C  
County: RICE Total Vertical Depth: 3320 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3170		
PROD	4.5	3319		75 SX
SURF	8.625	220		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2017 9:30 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM COMPANY Phone: (620) 786-8744

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/13/2017 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, HAD PARTED TUBING TO RECOVER. DID RECOVER TUBING WITH STUCK RODS. SET CIBP @ 3170' AND CAPPED WITH 2 SX'S CEMENT. PERFORATE AT 1000', 650', AND 270'. RUN TUBING TO 1000' AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING TO 650' AND WAITED 1.5 HOURS. ATTEMPT TO TAG CEMENT - COULD NOT. RUN TUBING BACK DOWN TO 1000' AND PUMPED 35 MORE SX'S COMMON WITH 3% CC. PULLED TUBING TO 650' AND LET SET 1.5 HOURS, TAGGED CEMENT AT 1150'. RUN TUBING BACK DOWN TO 1000' AND PUMPED ANOTHER 35 SX'S, PULLED TUBING OUT OF HOLE - TO COME BACK ON 12-13-17 AND TAG. TAGGED CEMENT AT 100-125' ON 12-13-17. RUN TUBING TO APPROX. 100' AND CIRCUALTED CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF. CONNECTED ONTO SURFACE CASING AND FILLED UP.

Perfs:

Top	Bot	Thru	Comments
3216	3227		CSG

INVOICED  
JAN 11 2018

Remarks: GRESSELL PERF #1643. COPELAND TICKET #45270. DENIED TA WELL - TA N.O.V.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

✓/8