

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22976-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 15-8S-22W
480 feet from N Section Line, 1310 feet from E Section Line
Lease Name: KEITH Well #: 15-1
County: GRAHAM Total Vertical Depth: 3640 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200TH AVE
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3638		150 SX
SURF	8.625	212		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2017 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE Company: RON'S OIL OPERATIONS INC DBA Phone: (785) 421-3640

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Port Collar at 1656' w/260 sx cement.
Perforations: 3320' - 3323'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2017 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3316' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 2718' and pumped 75 sx cement. Pulled tubing to 1742' and pumped 75 sx cement. Pulled tubing to 766' and pumped 44 sx cement. Pulled tubing out. Topped off casing with 5 sx cement. Backside is full of cement.

GPS: 39.36358 -099.75733

Perfs:

Top	Bot	Thru	Comments
3320	3323		

KCC WICHITA
DEC 04 2017
RECEIVED


INVOICED
JAN 11 2018

Remarks: SCHIPPERS CEMENT TICKET # 611

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

NOV 16 2017