

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-017-20148-00-00  
Spot: NWSENEW Sec/Twnshp/Rge: 6-19S-6E  
1665 feet from S Section Line, 3001 feet from E Section Line  
Lease Name: HARDER Well #: 9  
County: CHASE Total Vertical Depth: 500 feet

Operator License No.: 5192  
Op Name: SHAWMAR OIL & GAS CO., INC.  
Address: 1116 E MAIN PO BOX 9  
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	500		0 SX
SURF	4.5	120		20 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2017 12:00 AM  
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.  
Proposal Rcvd. from: BOB ROBINSON Company: SHAWMAR OIL & GAS CO., INC Phone: (620) 382-7565

Proposed Plugging Method: Run 1" to bottom. Circulate cement to surface. Pull 1" to 250' and circulate to surface.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/20/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

- 1) Dug out well, cemented in tubing/slim hole completion
- 2) Ran in hole with 1" tubing and tagged bottom at 515'
- 3) Mix up 15 sks cement (5 sks per bbl, no additives), pump down 1" tubing to 515' and circulate cement to surface
- 4) Pull tubing up to 250', circulate cement to surface
- 5) Pull tubing out of hole, top off hole with cement

INVOICED  
JAN 11 2018

Remarks: CEMENTING COMPLETED BY SHAWMAR OIL & GAS. PLUGGED PER COMPLIANCE AGREEMENT (16-CONS-4046-CMSC)

Plugged through: TBG

District: 02

Signed Jonathan Hill  
(TECHNICIAN)