

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-01765-00-02
Spot: NWSWSWSW Sec/Twnshp/Rge: 11-33S-5E
335 feet from S Section Line, 5203 feet from E Section Line
Lease Name: MADDIX Well #: 6
County: COWLEY Total Vertical Depth: 3134 feet

Operator License No.: 33372
Op Name: TAOS RESOURCES OPERATING COMP
Address: 1455 W LOOP S SUITE 600
HOUSTON, TX 77027

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3133		125 SX
SURF	8.625	150		60 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 11/17/2017 8:00 AM
Plug Co. License No.: 34422 Plug Co. Name: RED ROCK ENERGY SERVICES INC.
Proposal Rcvd. from: RAY DOROTHY Company: _____ Phone: (308) 340-4029

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 1838 W/2 SKS. PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/17/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 1838', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250'-251' (4 HOLES). RIH W/TUBING @ 258', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 133 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #54863.

Perfs:

Top	Bot	Thru	Comments
1888	1904	TBG	

INVOICED
JAN 17 2018

Remarks: FAILED MIT FOR TA STATUS

Plugged through: OH

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)