

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23726-00-00
Spot: N2S2SENW Sec/Twnshp/Rge: 29-31S-11W
3191 feet from S Section Line, 3337 feet from E Section Line
Lease Name: WHELAN Well #: V1-29
County: BARBER Total Vertical Depth: 4650 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4270		WITH 2 SX CMT
PROD	5.5	4610	3550	WITH 100 SX CMT
SURF	8.625	224		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2017 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 3270' WITH 2 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/15/2017 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4270' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 260' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4326	4332		

INVOICED
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
NOV 21 2017
KCC DODGE CITY

5A