

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23319-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 7-34S-10W
495 feet from N Section Line, 2145 feet from E Section Line
Lease Name: SMITH/MARKAM Well #: 1-7
County: BARBER Total Vertical Depth: 4820 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4490 | | WITH 2 SX CMT |
| PROD | 5.5 | 4819 | 3800 | WITH 125 SX CMT |
| SURF | 8.625 | 236 | | WITH 185 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2017 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4490' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 11/10/2017 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4490' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4653 | 4662 | | |
| 4636 | 4647 | | |

INVOICED
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Rypert
(TECHNICIAN)

RECEIVED
NOV 21 2017
KCC DODGE CITY

5A