

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23382-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 7-34S-10W
2145 feet from S Section Line, 3135 feet from E Section Line
Lease Name: GRIFFIN Well #: 1-7
County: BARBER Total Vertical Depth: 5126 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4595		WITH 2 SX CMT
PROD	5.5	4801	4040	WITH 100 SX CMT
SURF	8.625	227		WITH 195 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2017 11:15 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4590'. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 11/09/2017 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4595' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 608' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 266' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4648	4658		

INVOICED
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.
Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)
JA

RECEIVED
NOV 21 2017
KCC DODGE CITY
MD