

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-20662-00-00  
Spot: NENESE Sec/Twnshp/Rge: 1-11S-34W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: THRASHER Well #: 1-1  
County: LOGAN Total Vertical Depth: 4785 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4784		225 SX
SURF	8.625	344		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2017 9:30 AM  
Plug Co. License No.: 35052 Plug Co. Name: HUSKER ENERGY SERVICES, INC.  
Proposal Rcvd. from: DAVID VAN DYKE Company: VESS OIL CORPORATION DBA Phone: (316) 682-1537

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/550 # hulls.  
8 5/8" surface casing set at 344' w/225 sx cement.  
4 1/2" production casing set at 4784' w/225 sx cement.  
Stage collar set at 2655' w/370 sx cement.  
TD 4785', PBTD 4745'.  
Perforations: 4666' - 4672' (LKC)

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2017 1:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4600' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 3150' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1600' and pumped 115 sx cement w/100 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 25 sx cement. Connected to 8 5/8" surface casing and pumped 20 sx cement.

GPS: 39.12540N -101.03573W

Perfs:

Top	Bot	Thru	Comments
4666	4672		

INVOICED  
JAN 11 2018

Remarks: HUSKER ENERGY SERVICES INC. RIG AND BASIC ENERGY SERVICES CEMENT TICKET # 16,149

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

DEC 20 2017

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

DEC 18 2017