

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21714-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 31-22S-16W
859 feet from S Section Line, 501 feet from W Section Line
Lease Name: WARD FEED YARD Well #: 1-31
County: PAWNEE Total Vertical Depth: 4333 feet

Operator License No.: 34624
Op Name: VICTORY OPERATING, INC.
Address: PO BOX 908 223 E. PINE MEADOW CO
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4060		WITH 2 SX CMT
PROD	5.5	4333	2030	WITH 200 SX CMT
SURF	8.625	1062		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2017 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROSCOE MENDENHALL Company: VICTORY OPERATING Phone: (316) 648-5633

Proposed Plugging Method: CIBP @ 4060' WITH 2 SX CMT. PLUG AT 1090' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 30 SX CMT. PLUG AT 40-0' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2017 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4060' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1090' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT HOLDING AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
4180	4190		
4142	4168		
4114	4120		

INVOICED
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
NOV 22 2017
KCC DODGE CITY