

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-10146-00-00  
Spot: SWNENESW Sec/Twnshp/Rge: 34-29S-18W  
1986 feet from S Section Line, 3268 feet from E Section Line  
Lease Name: PARKIN Well #: 1  
County: KIOWA Total Vertical Depth: 4996 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 200 W DOUGLAS AVE #725  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3080		WITH 2 SX CMT
CIBP		3550		WITH 2 SX CMT
PROD	4.5	4994	0	WITH 100 SX CMT
SURF	8.625	414		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/04/2017 2:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: SPENCER SIROKY Company: FOSSIL DRILLING Phone: (620) 770-0636

Proposed Plugging Method: CIBP @ 4994' WITH 2 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 464' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/04/2017 4:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CASING LEAK AT 3190'-3193'. COULD NOT GET CIBP PAST 3550' SO SET IT THERE WITH 2 SX CMT. SET 2ND CIBP @ 3080' WITH 2 SX CMT. SHOT CASING OFF AT 1118' BUT COULD NOT GET FREE. PERFORATED AT 1115'. TIED ONTO CASING & PUMPED 15 SX GEL, THEN DISPLACED 50 SX CMT (25 SX INSIDE & 25 SX OUTSIDE OF PERFORATIONS). PERFORATED AT 464'. TIED ONTO CASING & CIRCULATED CMT TO SURFACE WITH 170 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4970	4974		
4954	4960		


INVOICED  
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
DEC - 11 2017  
KCC DODGE CITY

