

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21199-00-00
Spot: SENWNESW Sec/Twnshp/Rge: 26-28S-18W
2000 feet from S Section Line, 3312 feet from E Section Line
Lease Name: AHRENS Well #: 1
County: KIOWA Total Vertical Depth: 4980 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4725		WITH 25 SX CMT
L1	4.5	4859		TOP OF LINER 4776' WITH 35 SX CMT
PROD	5.5	4970	0	WITH 150 SX CMT
SURF	8.625	477		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/30/2017 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: SPENCER SIROKY Company: FOSSIL DRILLING Phone: (620) 770-0636

Proposed Plugging Method: SET CIBP @ 4725' WITH 2 SX CMT. PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT. PLUG AT 520' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2017 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

NO CASING RECOVERED DUE TO PRODUCTION & SURFACE CASING BEING UNSTABLE AT THE SURFACE. SET CIBP @ 4725' WITH 2 SX CMT. PERFORATED AT 1220'. TIED ONTO 5 1/2" CASING & ESTABLISHED A PUMP RATE OF 2.5 BPM @ 500# THEN DISPLACED 25 SX CMT OUTSIDE THE PERFORATIONS & 25 SX CMT INSIDE THE 5 1/2" CASING AT 1220'. PERFORATED AT 520'. CIRCULATED CMT TO SURFACE WITH 150 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4860	4870		


INVOICED
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
DEC - 5 2017
KCC DODGE CITY

