

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21638-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 21-29S-18W
1895 feet from S Section Line, 1884 feet from W Section Line
Lease Name: YOST A Well #: 1-21
County: KIOWA Total Vertical Depth: 4962 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4860 | | WITH 2 SX CMT |
| PROD | 4.5 | 4910 | 2024 | WITH 100 SX CMT |
| SURF | 8.625 | 508 | | WITH 300 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/01/2017 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: SPENCER SIROKY Company: FOSSIL DRILLING Phone: (620) 770-0636

Proposed Plugging Method: SET CIBP @ 4860' WITH 2 SX CMT. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: PARTIAL
Date/Time Plugging Completed: 12/01/2017 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4860' WITH 2 SX CMT. 1ST PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4910 | 4962 | | |

INVOICED
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
DEC - 5 2017
KCC DODGE CITY