

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20653-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 32-30S-9W
1840 feet from S Section Line, 4650 feet from E Section Line
Lease Name: JACOBS M Well #: 1
County: KINGMAN Total Vertical Depth: 4348 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4340	1870	125 SX
SURF	8.625	235		185 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/15/2017 12:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: PAT LIVINGSTON Company: _____ Phone: (620) 388-6143

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/23/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP AT 4300' AND SPOTTED 2 SX CEMENT ON TOP OF CIBP. SHOT OFF 4.5" CASING AT 1870', TRIPPED OUT OF THE HOLE WITH CASING, RECOVERED 59 JOINTS OF 4.5" CASING. 8/17/2017 - TRIPPED BACK IN HOLE WITH 2" TUBING TO 1585' AND PUMPED A 50 SX PLUG (3% CC). SET FOR 1 1/2 HOURS AND THEN TRIPPED BACK IN HOLE TO TAG CEMENT AT 1385'. PULLED UP TO 985' AND PUMPED 35 SX (60/40 POZ, 4% GEL & 3% CC). PULLED UP TO 300' AND PUMPED 130 SX (60/40 POZ, 4% GEL & 3% CC), CEMENT DID CIRCUALTE TO SURFACE. 8/23/2017 ROUSTABOUT SERVICE TOPPED OFF CEMENT IN SURFACE CASING WITH 6 SX PORTLAND CEMENT. USED A TOTAL OF 50 SX COMMON AND 165 SX 60/40 POZ.

Perfs:

Top	Bot	Thru	Comments
4340	4348		

INVOICED
JAN 11 2018

Remarks: QUALITY WELL SERVICE CEMENTING INVOICE #6704. TOP OFF WITH 6 SX PORTLAND BY PRATT WELL SERVICE. INV. #16641.

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN)