

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20468-00-00
Spot: SENWENW Sec/Twnshp/Rge: 26-29S-8W
4945 feet from S Section Line, 3370 feet from E Section Line
Lease Name: PLUSH Well #: 2
County: KINGMAN Total Vertical Depth: 4184 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4174	1325	100 SX
SURF	8.625	248		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/18/2017 12:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: PAT LIVINGSTON Company: _____ Phone: (620) 388-6143

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 08/23/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

8/22/17 CIBP SET AT 4116'. SPOTTED 2 SX CEMENT ON CIBP. SHOT CASING AT 1612', WOULD NOT COME FREE. SHOT CASING AT 1500', WOULD NOT COME FREE. SHOT CASING AT 1325' AND PULLED FREE. AT ABOUT 1260' GAS BLEW FLUID OUT OF HOLE & CROWNED RIG, KILLED WELL. PULLED UP TO 1200' AND PUMPED 12 SX GEL, IN FRONT OF 50 SX COMMON (3% CC). PULLED UP AND LET CEMENT SIT. RAN IN WITH CASING SWAB AND TAGGED CEMENT AT 925'. PULLED UP TO 692' AND PUMPED 35 SX 60/40 POZ (4% GEL). PULLED UP 300' AND PUMPED 125 SX 60/40 POZ (4% GEL) WITH CEMENT CIRCULATING TO SURFACE.
8/23/2017 -ROUSTABOUT SERVICE TOPPED OFF CEMENT IN SURFACE CASING WITH 6 SX PORTLAND CEMENT. USED A TOTAL OF 50 SX COMMON AND 160 SX 60/40 POZ.

Perfs:

Top	Bot	Thru	Comments
4174	4184		

INVOICED
JAN 11 2018

Remarks: QUALITY WELL SERVICE- CEMENTING INVOICE #6700. TOP OFF WITH 6 SX PORTLAND BY PRATT WELL SERVICE INVOICE #16642.

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)