

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20991-00-00
Spot: NESESWSW Sec/Twnshp/Rge: 24-29S-41W
605 feet from S Section Line, 4046 feet from E Section Line
Lease Name: FISS Well #: 1
County: STANTON Total Vertical Depth: 5723 feet

Operator License No.: 33856
Op Name: WHITE EXPLORATION, INC.
Address: 1635 N. WATERFRONT PKWY SUITE 1
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5723	1730	WITH 175 SX CMT
SURF	8.625	1654		WITH 620 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2017 9:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: SET CIBP @ 5370' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2017 3:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 5370' WITH 2 SX CMT. 1ST PLUG AT 1690' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 596' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 28 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5466	5498	CSG	
5438	5446	CSG	
5430	5430		

INVOICED
JAN 11 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

District: 01

Signed _____

Heith Walsh
508

(TECHNICIAN)

RECEIVED
NOV 21 2017
KCC DODGE CITY

MD