

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-22576-00-00
Spot: SESE Sec/Twnshp/Rge: 32-18S-24W
682 feet from S Section Line, 681 feet from E Section Line
Lease Name: MINER Well #: 1
County: NESS Total Vertical Depth: 4461 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 14216 N US HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1425		WITH 200 SX CMT
PROD	5.5	4456	0	WITH 100 SX CMT
SURF	8.625	657		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2017 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: BOTTM PLUG AT 4350' WITH 35 SX CMT & 100# HULLS. PULL TBG TO 1640' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2017 12:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP 35 SX CMT & 100# HULLS AT 4350'. PULL TBG TO 1650' & CIRCULATE CMT TO SURFACE WITH 180 SX CMT. PULL TBG & TOP OFF WITH 15 SX CMT. PUMPED 20 SX CMT DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
4391	4395		
4380	4386		

INVOICED
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Larry Harris ECRS
(TECHNICIAN)

RECEIVED
NOV 20 2017
KCC DODGE CITY