

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22566-00-01  
Spot: NESWNW Sec/Twnshp/Rge: 30-34S-14W  
3636 feet from S Section Line, 4139 feet from E Section Line  
Lease Name: Z BAR CATTLE COMPANY Well #: 6  
County: BARBER Total Vertical Depth: 5680 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4846		WITH 2 SX CMT
CIBP		5305		
PROD	5.5	5674	690	WITH 175 SX CMT
SURF	10.75	223		WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2017 3:30 PM  
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.  
Proposal Rcvd. from: LARRY DREILING Company: WOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: CIBP @ 5260' WITH 2 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 70 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/08/2017 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4846' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG 690' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 65 SX CMT. 11/9/17: FOUND TOC @ 80'. TOPPED OFF WITH READY MIX.

Perfs:

Top	Bot	Thru	Comments
5312	5320		

INVOICED  
JAN 11 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED  
NOV 21 2017  
KCC DODGE CITY

SA