

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217  
NORTH

Ness County, Sec 24 Twp. 20S Rge. ~~21~~ 21(W)

Location as "NE/CNW/SW" or footage from lines APPROX NE NE

Lease Owner Davis & Reed

Lease Name Isern Well No. 2

Office Address 645 4th Fin Cnt Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1/2/76 19

Application for plugging filed 1/2/76 19

Application for plugging approved 1/2/76 19

Plugging commenced 1/2/76 19

Plugging completed 1/2/76 19

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4411 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	304.68'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 550'. Set plug. Put in 70 sacks cement. Filled with heavy mud to 240'. Set plug. Put in 20 sacks cement. Filled with heavy mud to 40'. Set plug. Filled to top with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
1-12-76  
JAN 12 1976  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor G-G Drilling Co.

Address 1107 Union National Bldg Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway 1107 Union Natl Bldg  
Wichita, Kansas 67202

Subscribed and sworn to before me this 6th day of January, 1976

PHYLLIS BUCHANAN  
NOTARY PUBLIC  
My commission expires Dec. 8, 1979

Phyllis Buchanan  
Notary Public.


**KANSAS DRILLERS LOG**

S. 24 T. 20SR. 21 <sup>E</sup>/<sub>W</sub>

Loc. APPROX NE NE

County NESS

640 Acres  
N



Locate well correctly

Elev.: Gr. \_\_\_\_\_

DF \_\_\_\_\_ KB 2224'

API No. 15 — 135 — 21140-0000  
 County Number

Operator DAVIS & REED

Address 645 4th FINANCIAL CENTER WICHITA, KS 67202

Well No. 2 Lease Name ISERN

Footage Location  
330 feet from (N) (S) line 330 feet from (E) (W) line

Principal Contractor C-G DRILLING CO Geologist GEORGE A REED

Spud Date 12/21/75 Total Depth 4411' P.B.T.D. \_\_\_\_\_

Date Completed 1/2/76 Oil Purchaser \_\_\_\_\_

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (In O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4"	8 5/8"	28#	304.68	POZMIX	185	2% GEL + 3% CALC CLORIDE

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production \_\_\_\_\_ Producing method (flowing, pumping, gas lift, etc.) \_\_\_\_\_

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval(s) \_\_\_\_\_

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS,  
 DRY HOLE, SWDOW, ETC.:  
**DRY HOLE**

Operator  
**DAVIS & REED**

Well No. **2** Lease Name **ISERN**

s **24** T **20** SR **21** W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SHALE	0	130		
SAND & SHALE	130	304		
SHALE	304	855		
SAND	855	1065		
RED BED & SHALE & SAND	1065	1255		
SHALE	1255	1394		
ANHYDRITE	1394	1432		
SHALE & SHELLS	1432	2110		
SHALE & LIME	2110	2315		
LIME & SHALE	2315	3890		
LIME	3890	4390		
MISSISSIPPI	4390	4402		
LIME	4402	4411		

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 12 1976  
 CONSERVATION DIVISION  
 Wichita, Kansas

DST #1: 4325-4390' OP 20 SI 30  
 REC 15' MUD. IFP 82#, FFP 102#.  
 NO BOTTOM HOLE PRESSURE.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Phyllis Buchanan*  
 Signature **Phyllis Buchanan**  
 Office Manager  
 Title  
 1/2/76  
 Date