

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15,135,20076,0000

LEASE NAME Isern #1

WELL NUMBER SE NE

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 24 TWP. 20s RGE. 21e (E) or (S)

COUNTY Ness

Date Well Completed

Plugging Commenced 6/27/85

Plugging Completed 7/1/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Braden-Deem, Inc.

ADDRESS 125 N. Market, Suite 1250, Wichita, Ks. 67202

PHONE#(316) 265-1731 OPERATORS LICENSE NO. 5331

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4397'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	442'	none
				4 1/2"	4396'	2387'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 4330' & 4 sacks cement. Shot pipe at 3000', 2800', & 2600', & 2387'. Pulled 72 joints of pipe. Plugged well with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 150 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling STATE CORPORATION COMMISSION 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 85

Irene Hoover
 Notary Public

My Commission Expires:



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

A. & O. ISERN #1
 C SE NE SECTION 24-20S-21W
 NESS COUNTY, KANSAS

COMMENCED: OCTOBER 25, 1967
 COMPLETED: NOVEMBER 3, 1967

OPERATOR - CHAMPLIN PETROLEUM Co.

DEPTH	FORMATION	REMARKS
FROM	To	
0	40	SURFACE CLAY
40	443	SHALE AND SHELLS
		RAN 11 JOINTS 8-5/8" CASING, SET @ 442' w/250 BAGGS CEMENT.
443	545	SHALE
545	900	SHALE AND RED BED
900	1075	SAND
1075	1420	RED BED
1420	1450	ANHYDRITE
1450	2020	SHALE
2020	2275	SHALE, LIME AND SHELLS
2275	2375	LIME AND SHALE
2375	2600	LIME
2600	4070	SHALE AND LIME
4070	4280	LIME
4280	4387	LIME AND SHALE
4387	4397	LIME
4397	TO	
		RAN 135 JOINTS 4 1/2" CASING, SET @ 4396 1/2 FT. w/150 BAGGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SE NE SECTION 24-20S-21W, NESS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 6TH DAY OF NOVEMBER, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.



RECEIVED
 STATE CORPORATION COMMISSION

APR 11 1985

CONSERVATION DIVISION
 Wichita, Kansas

XERO COPY

XERO COPY

XERO COPY