


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec. 17 Twp. 20S Rge. (E) 23(W)

Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Schreiner Petroleum
Lease Name Johnson Well No. 1
Office Address 207 Petroleum Building - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 7-15 19 68
Application for plugging filed 7-16 19 68
Application for plugging approved 7-16 19 68
Plugging commenced 1:00 7-16 19 68
Plugging completed 3:00 7-16 19 68
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation none Depth to top Bottom Total Depth of Well 4402 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	329	8 5/8"	329	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with 70 sacks at 600' 20 sacks at 300'
10 sacks at 40' 2 sacks in rat hole.
Plugged by Globe & Leo Massey

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor B & B DRILLING, INC.
Address 207 Petroleum Building - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahat (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahat
207 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of July, 19 68
May 31, 1970

Alma G. Neesen
Notary Public.

B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

July 20, 1968

DRILLERS LOG

Re: Johnson #1
 C SE NW Sec. 17-20S-23W
 Ness County, Kansas

COMPANY: Schreiner Petroleum
 CONTRACTOR: B & B Drilling, Inc.
 TOTAL DEPTH: 4402'
 COMMENCED: July 5, 1968
 COMPLETED: July 16, 1968

0	80	Soil & Shale - Lime	
80	330	Shale & Shells	
330	730	Shale	
730	1415	Red Bed & Shale	
1415	1515	Shale	
1515	1553	Anhydrite	
1553	1930	Shale & Lime	
1930	2170	Shale & Lime	
2170	2365	Shale & Lime	
2365	2525	Shale & Lime	
2525	2615	Lime	
2615	2850	Lime	
2850	3420	Lime & Shale	
3420	3845	Lime & Shale	
3845	4120	Lime	
4120	4190	Lime	
4190	4273	Lime & Shale	
4273	4284	Lime	DST #1
4284	4293	Lime	
4293	4358	Lime-Cherty	
4358	4380	Lime	DST #2
4380	4386	Lime	
4386	4392	Lime	DST #3
4392		Lime	DST #4
4392	4393		Log
4392	4402	Lime & Chert	DST #5
4402		Total Depth	D & A

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 22 1968
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Johnson, located in Ness County, Kansas.

Bill Baker President

Alma A. Neiser Notary Public

Subscribed and sworn to before me this 20th day of July, 1968. My commission expires May 31, 1970