

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 17 Twp. 20S Rge. 23W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NE SW

Lease Owner Strata Drilling Company
Lease Name Lehner Well No. #1

Office Address Box 355, Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry hole

Date Well completed May 12, 1977 19

Application for plugging filed May 12, 1977 19

Application for plugging approved May 12, 1977 19

Plugging commenced May 12, 1977 19

Plugging completed May 12, 1977 19

Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	295	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Hole plugged as follows: plugged @ 630' with 70 sacks 50-50 pozmix, 6% gel; plugged at 240' with 20 sacks, 50-50 pozmix, 6% gel; plugged @ 40' with 10 sacks 50-50 pozmix, 6% gel. Plug down 8:00 p.m., May 12, 1977.

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.
Kenneth J. Link (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President
Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1977.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-80



D R I L L E R S L O G

#1 Lehner

CASING RECORD: 290.30' used 24# 8-5/8" surface casing	COMPANY: Strata Drilling Company	DESCRIPTION: NE NE SW Section 17-20S-23W Ness County, Kansas
TOTAL DEPTH: 4390'	CONTRACTOR: Strata Drilling Company	ELEVATION: 2271' GL
	COMMENCED: May 4, 1977	
	COMPLETED: May 12, 1977	

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil and shale	0	310	Ran 290.30' of used 24# 8-5/8" surface casing; set and cemented @ 295' with 185 sacks common cement, 2% gel, 3% C.C.; cement circulated; plug down @ 1:15 a.m., May 5, 1977.
Shale and red bed	310	1518	
Anhydrite	1518	1548	
Shale	1548	2180	
Lime and Shale	2180	3970	
Lime	3970	4030	Ran 5 Drill Stem Tests
Lime and shale	4030	4364	
Mississippi	4364	4390	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 19 1977
 CONSERVATION DIVISION
 Wichita, Kansas

Hole plugged as follows: plugged @ 630' with 70 sacks 50-50 pozmix, 6% gel; plugged at 240' with 20 sacks 50-50 pozmix, 6% gel; plugged @ 40' with 10 sacks 50-50 pozmix, 6% gel. Plug down 8:00 p.m., May 12, 1977.

STATE OF KANSAS)
) ss
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link

 Kenneth J. Link, President

Subscribed and sworn to before me this 18th day of May, 1977.

My Commission expires: March 28, 1980.

Loneita Barry

 Loneita Barry, Notary Public

