

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 16 Twp. 20 Rge. (E) 23 (W)

Location as "NE/CNW%SW%" or footage from lines C NW NE

Lease Owner Pickrell Drilling Company

Lease Name Mauch Well No. 1

Office Address 705 4th National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 13, 19 65


Application for plugging filed November 13, 19 65

Application for plugging approved November 13, 19 65

Plugging commenced November 13, 19 65

Plugging completed November 13, 19 65

Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4460 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 540', set plug, cemented with 20 sacks cement. Heavy mud to 220', set plug, cemented with 20 sacks cement. Heavy mud to 40', set plug, cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company

Address 705 4th National Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) C. W. Sebits

705 4th National Bank Bldg, Wichita, Kansas (Address)

Subscribed and sworn to before me this 16th day of November, 1965



Maxine Blackman, Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced: 11-3--65

LOCATION: Mauch No. 1, C NW NE Section 16-20-23W, Ness County, Kansas

Rotary Drilling Completed: 11-13-65

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: (11 jts) 8 5/8" surface casing set at 245' cemented with 155 sacks cement. Circulated. Completed 5:00 P.M. November 3, 1965.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

45	Post Rock	<u>C. F. S.</u>
1550	Shale & Shells	4342
1900	Shale & Lime Stringers	4435
2700	Lime & Shale	4445
3708	Lime	4460
3380	Shale & Lime	
3506	Sandy Lime & Shale	
3745	Shale & Lime	<u>Slope Tests</u>
3785	K. C. Lime	2500
3877	Lime & Shale	3000
4010	Lime	3500
4100	Lime & Shale	4000
4160	Lime	
4290	Lime & Shale	<u>S. L. M.</u>
4342	Lime	3548
4390	Lime & Shale	3877
4460	Mississippian - RTD	4207

RECEIVED
STATE OPERATIONAL COMMISSION
NOV 18 1965

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebits, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 16th day of November, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

I have under my hand and seal of office the day and year last above written.

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public