


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Ness County, Sec. 16 Twp. 20S Rge. 23W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner L. D. Davis  
Lease Name Mauch Well No. #1  
Office Address P. O. Box 324, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed February 5, 1980 19  
Application for plugging filed February 5, 1980 19  
Application for plugging approved February 5, 1980 19  
Plugging commenced February 5, 1980 19  
Plugging completed February 5, 1980 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation Depth to top Bottom Total Depth of Well 4455 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 830',  
20 sacks @ 510', hulls and 10 sacks @ 40'; job completed  
at 5:30 a.m., February 5, 1980.

RECEIVED  
STATE CORPORATION COMMISSION  
2-27-80  
FEB 27 1980

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Strata Drilling Company  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.  
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of February, 1980

Loneita Barry  
Notary Public.



D R I L L E R S    L O G

#1 Mauch

CASING RECORD: 14 jts. used 8-5/8" surface casing	COMPANY: L. D. Davis	DESCRIPTION: NE NE NE Section 16-20S-23W Ness County, Kansas
	CONTRACTOR: Strata Drilling Company	
TOTAL ROTARY DEPTH: 4455'	COMMENCED: January 29, 1980	ELEVATION: 2283' KB
	COMPLETED: February 5, 1980	

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale	0	538	Ran in 527' used 8-5/8" surface casing; set and cemented at 532' with 350 sacks common, 2% gel, 3% C.C. Cement circulated. Plug down at 6:15 p.m., January 30, 1980.
Shale	538	1515	
Anhydrite	1515	1545	
Shale	1545	2490	
Lime and shale	2490	3305	
Lime	3305	3535	
Lime and shale	3535	3995	
Lime	3995	4300	
Lime and shale	4300	4390	
Lime	4390	4455	

STATE OF KANSAS )  
                          )ss  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Charles W. Steincamp*  
Charles W. Steincamp

Sworn to and subscribed before me this 25th day of February, 1980.

My appointment expires: 3-28-80.

*Loneita Barry*  
Loneita Barry, Notary Public

