

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ness County, Sec. 13 Twp. 20S Rge. (E) 24 (W)

Location as "NE/CNW%SW%" or footage from lines C/SW NW

Lease Owner R. V. Lehner

Lease Name Petersilie Well No. 4

Office Address P. O. Box 398, Ness City, Kansas 67560

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 26 19 68

Application for plugging filed November 26 19 68

Application for plugging approved November 26 19 68


Plugging commenced November 26 19 68

Plugging completed November 26 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4424 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 8-5/8", 0, 368'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 660' with 70 sacks of cement; plugged at 360' with 20 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 6:20 P. M. November 26, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas


Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss. Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of November, 19 68

My commission expires December 14, 1969



Elaine H. Taylor Notary Public

D R I L L E R S    L O G

#4 Petersilie

CASING RECORD: 368' of new 8-5/8" surface casing.	COMPANY: R. V. Lehner	DESCRIPTION: C/SW NW Section 13-T20S-R24W Ness County, Kansas
TOTAL DEPTH: 4424'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2304' DF
	COMMENCED: November 18, 1968	
	COMPLETED: November 26, 1968	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Rock Post	0	80	Ran 368' of new 8-5/8" surface casing; set and cemented at 368' with 185 sacks of common cement and 2% gel. Plug down at 8:20 A. M. November 19, 1968.
Clay & Shale	80	140	
Shale, Red Bed, & Shells	140	924	
Shale & Red Bed	924	1003	
Sand	1003	1252	
Shale, Shells & Red Bed	1252	1400	
Sand	1400	1409	
Shale	1409	1439	
Shale, Shells & Anhydrite	1439	1788	
Shale & Lime	1788	3660	
Lime & Chert	3660	4407	
Cherty Lime	4407	4424	

Total Depth 4424'

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 660' with 70 sacks of cement; plugged at 360' with 20 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 6:20 P. M. November 26, 1968.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp  
Charles W. Steincamp, President

Subscribed and sworn to before me this 27th day of November, 1968.

My Commission Expires:  
December 14, 1969

Elaine H. Taylor  
Elaine H. Taylor, Notary Public

