


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 13 Twp. 20S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines C/SW NE
Lease Owner R. V. Lehner
Lease Name Petersilie Well No. 5
Office Address P. O. Box 398, Ness City, Kansas 67560
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 7 1968
Application for plugging filed December 7 1968
Application for plugging approved December 7 1968
Plugging commenced December 7 1968
Plugging completed December 7 1968
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4449 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	368.42'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Plugged hole as follows: Plugged hole at 660' with 70 sacks of cement; plugged at 360' with 20 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 8:30 A. M. December 7, 1968.


RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of December, 1968



December 14, 1969
Elaine H. Taylor Notary Public.

D R I L L E R S L O G

#5 Petersilie

CASING RECORD:
364.50' with new 8-5/8"
surface casing.

COMPANY: R. V. Lehner
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW NE
Section 13-20S-24W
Ness County, Kansas

TOTAL DEPTH:
4449'

COMMENCED: November 29, 1968
COMPLETED: December 7, 1968

ELEVATION: 2329' DF

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	210	Ran 364.50' of new 8-5/8" surface casing; set and cemented at 368.42' with 170 sacks of common cement and 2% gel. Plug down at 9:25 P. M. November 29, 1968.
Shale, Sand &	210	375	
Shale, Sand & Anhydrite	375	1375	
Shale, Shell & Red Bed	1375	1563	
Anhydrite	1563	1589	
Red Bed, Shells & Shale	1589	1875	
Shale, Shells & Lime	1875	2339	
Shale & Lime	2339	3947	
Lime	3947	4472	
Cherty Lime	4472	4419	
Chert & Lime	4419	4449	

Total Depth 4449'

D. & A.

Plugged hole as follows: Plugged at 660' with 70 sacks of cement; plugged at 360' with 20 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 8:30 A. M. December 7, 1968.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

My Commission Expires:
December 14, 1968

Elaine H. Taylor
Elaine H. Taylor, Notary Public

Subscribed and sworn to before me this 9th day of December, 1968.