



15.185.30279.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS-67202

RECEIVED  
STATE CORPORATION COMMISSION

JAN 17 1966

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. George Sowles of Abercrombie Drilling, Inc has this date requested permission to plug the following described well:

Mr. Sowles guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: Linke Well No. # 1

Location: C NW NE NW Sec. 27 Twp. 21 Rge. 13 (E)(W) W

County Stafford Total Depth 2026' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole X

Mr. Sowles was instructed to plug the well as follows:

247' of 8 5/8" surface pipe, cement circulated with 225 sacks.  
Fill hole with drilling mud to 200', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Archie Elving*

Conservation Division Agent