

State of Kansas



15.135.21169.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. French of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. Co.

Complete Address: 205 Litwin Bldg., Suite 205, Wichita, Ks.

Lease Name: Hair-Lundy Well No. 2

Location: 150' E. off SW NE Sec. 2 Twp. 20 Rge. (E)(W) 24

County: Ness Total Depth 4457' Oil Well

Gas Well Input Well SWD Well D & A EX Lost Hole

Mr. French was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill
pipe. Heavy mud to 250' set 20 sk gem plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Les Massey
Conservation Division Agent