

State of Kansas



15.135.30205.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

RECEIVED
STATE CORPORATION COMMISSION

JUN - 6 1966

CONSERVATION DIVISION
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Musgrove of Hellar Drl. Co. has this
date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Marmik Oil Co.

Complete Address: 110 west Elm St. El Dorado, Ark.

Lease Name: William C. Wells Well No. 2

Location: 150 Ft. So. SE - NW Sec. 25 Twp. 20 Rge. 21 (E)(W) X

County Ness Total Depth 4420 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 550 Ft. and
displace 25 sax cement thru drill pipe. Heavy mud to 240 Ft. set
cementing plug, and displace 20 sax cement thru drill pipe. Heavy
mud to 40 Ft. set cementing plug, 1/3 sax hulls, and 10 sax cement
to base of cellar. Plug rat hole with 2 sax cement.

Very truly yours,

Leo Massey
Conservation Division Agent