

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.145.00082.0000

LEASE NAME Stalcup-Jones #1

WELL NUMBER _____

SPOT LOCATION SE SE NE

SEC. 33 TWP. 21 RGE. 16w (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 1/30/84

Plugging Completed 2/2/84

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center, Wichita, Ks. 67202

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3874'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1013 77'	none
				5 1/2"	3855'	2481'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Ran sand to 3800' & 5 sacks cement. Shot pipe at 2909', 2723', & 2505'. Pulled total of 78 joints of 5 1/2". Plugged well with 3 hulls, 10 gel, 50 cement, 7 gel, 1 hull, released plug & 125 sacks 60/40 poz 2% gel 3% e.e.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks, 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

FEB 08 1984

SUBSCRIBED AND SWORN TO before me this 7th day of February, 1984



Irene Hoover
Notary Public

CONSERVATION DIVISION
Wichita, Kansas expires: _____

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: JONES - STALCUP #1
 LOCATION: 1080' South of the N/L
 242.5' West of the E/L
 Pawnee County, Kansas

COMMENCED: January 10, 1953
 COMPLETED: January 20, 1953

0	90	Sand
90	185	Sandy clay
185	417	Shale
417	520	Sand
520	677	Shale and sand
677	875	Shale
875	915	Shale and shells
915	967	Shale
967	975	Red bed
975	1000	Shale and anhydrite
1000	1351	Lime and shale
1351	1820	Shale and shells
1820	1900	Anhydrite and shale
1900	2400	Lime and shale
2400	2705	Shale, lime and shells
2705	2820	Shale and shells
2820	2930	Shale and lime
2930	3160	Shale and shells
3160	3565	Shale and lime
3565	3828	Lime
3828	3851	Conglomerate
3851	3857	Arbuckle lime
	3857	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 4 5 1963
 CONSERVATION DIVISION
 Wichita, Kansas

Set 1013.77 of 8 5/8" cemented with two sacks of cement.
 Set 5 1/2" at 3855' cemented with 150 sacks of cement.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the JONES-Stalcup #1, Section 1080' South of the W/L and 242.5 West of the E/L Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION
 By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for Sedgwick County, Kansas, this 28th day of January, 1953.

Mary Ann
 Notary Public

My Commission Expires: November 14, 1956.