

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.30278.0000

LEASE NAME Linke

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 21 RGE. 13W (E or W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 5-16-91

Plugging Completed 6-3-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS RT #1 Box 56 Great Bend, KS. 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3695'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	320'	none
				4 1/2"	3669'	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3400', dumped 4 sacks cement. Shot pipe @2700', 2600', 2500'. Plugged with 300# hulls, 10 gel, 50 cement, 10 gel, 100# hull, 100 sacks 60/40 6% gel. Max pressure 500#, Shut In 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A.L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 6 day of June, 19 91

Irene Herzberg
Notary Public

My Commission Expires:



JUN 07 1991

REGISTRATION DIVISION
Wichita, Kansas

OFF

RECEIVED
REGISTRATION COMMISSION

CONTRACTOR'S WELL LOG

COMPANY:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
FARM:	LINE #1
LOCATION:	NW NE NW Sec. 27-21W-13W Stafford County, Kansas
COMMENCED:	January 15, 1966
COMPLETED:	January 26, 1966

0	94	Sand
94	151	Hard Sand
151	156	Shale
156	320	Shale-Pyrite
320	723	Shale
723	747	Anhydrite
747	1150	Shale
1150	1550	Shale-Shellis
1550	1615	Shale
1615	1815	Lime
1815	1909	Lime & Shale
1909	2630	Shale & Lime
2630	3343	Lime & Shale
3343	3585	Lime
3585	3610	Lime - Chert
3610	3670	Lime
	3670	Rotary Total Depth

Set 8-5/8" surface at 320' w/275 sx cement

Set 4-1/2" production casing at 3669' w/150 sx cement

ELEVATION: 1884' K. B.

ELECTRIC LOG TOPS:

Anhydrite	722'	(+ 1162)
Hebner	3195'	(- 1311)
Lansing	3335'	(- 1451)
Arbuckle	3668'	(- 1784)
Rotary T. D.	3670'	(- 71784)

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Mildred Saxton, do hereby certify that the above and foregoing is a true and correct copy of the log of the LINE #1, NW NE NW Sec. 27-21W-13W, Stafford County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

Mildred Saxton
Mildred Saxton, Secretary

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 31st day of January, 1966.

Leah Faye Hefko
Leah Faye Hefko, Notary Public

My commission expires June 16, 1967

RECEIVED
STATE CORPORATION COMMISSION

MAY 08 1991

CONSERVATION DIVISION
Wichita, Kansas