

15.185.01747.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A 9-7-57

LEASE NAME Gates

WELL NUMBER 16

4950 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 27 TWP. 23S RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 10-11-57

Plugging Commenced 9-9-91

Plugging Completed 9-10-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Liedtke Operating Corporation

ADDRESS 370 17th Street, Suite 5020, Denver CO 80202

PHONE#(303) 595-8405 OPERATORS LICENSE NO. 20385

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 30, 1991 (date)

by Richard Lacey (Dwayne Rankin, Field Agent) (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, Is well log attached? no

Producing Formation Lansing & Arbuckle Depth to Top 3306' Bottom 3700' T.D. P.B.3610'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Meade	Water	80'	130'	10-3/4"	249'	none
Lansing	Oil	3306'	3530'	7"	3700'	none
Arbuckle	Oil	3632'	3700'	7"	3700'	none

SEP 13 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perf. 4 shots @ 705'. Tubing @ 3600', pump 2 sks. hulls, 75 sks. common, 4% C.C. Pull tubing to 3510', displace plug. Pull tubing to 3240', run gel spacer to 700'. Pull tubing to 740' pump more gel to surface. Pump 385 sks. 60-40 poz mix, 6% gel. Cement circulated to surface, 10 3/4" and 7" casing. Pull tubing, top off 25 sks 60-40 poz mix, 6% gel.

(If additional description is necessary, use BACK of this form.)
9/10/91 Cement 7" from surface in 7", 14' from surface 10 3/4". Fill with Ready-mix.

Name of Plugging Contractor Chase Well Service, Inc. License No. 6123

Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON, ss.

Charles W. Steincamp (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles W. Steincamp

(Address) P. O. Box 355, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 91

Loneita Barry
Loneita Barry Notary Public

