

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15.185.01746.0001

API NUMBER Spud 12-11-56

LEASE NAME Gates Unit

WELL NUMBER 15

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 21S RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3-30-94

Plugging Completed 4-7-94

TYPE OR PRINT
 NOTICE: Fill out completoly
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Globe Exploration, Inc.

ADDRESS P. O. Box 12 Great Bend, KS 67530-0012

PHONE# (316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 13 3/8 | 252' | none |
| | | | | 7" | 3643' | 1600' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3260' & dumped 7 sks cement. Shot well @ 2000', 1900', 1700', worked pipe & left on tension. Shot well @ 1600', pipe came free. Pulled pipe. Plugged well with 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 125 sks cement. Shut in @ 100# psi. Max 700# psi. 60/40 poz 6% gel. Plugging complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Owner)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 94

Irene Herzberg
 Notary Public

My Commission Expires:



Form CP-4
 Revised 05-88

RECEIVED
 STATE CORPORATION COMMISSION
 APR 13 1994

CONSERVATION DIVISION
 Wichita, Kansas