


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County. Sec. 9 Twp. 20 Rge. 24 (E) (W)
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines C NW NW
Lease Owner Pickrell Drilling Company
Lease Name McCreight A Well No. 1
Office Address 2820 Paseo Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed July 20, 1962 19____
Application for plugging approved July 22, 1962 19____
Plugging commenced August 10, 1962 19____
Plugging completed August 16, 1962 19____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4494 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	284	none
				5 1/2	none	2540

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured T.D. and sanded to 4300'. Dumped 5 sacks cement and worked pipe. Shot @ 3702'.

Worked pipe and circulated. Spotted 80 bbl. oil. (Globe Truck)

Worked pipe and shot @3500-3200-3000-2700'. Fished out shooting line.

Worked pipe and shot @2600-2510'. Pulled pipe.

Pulled pipe and circulated 20 sacks cement and 15 sacks mud @500'. Pulled pipe and pumped in 20 sacks cement and pulled pipe and capped well with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1962
9-12-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kas
(Address)

SUBSCRIBED AND SWORN to before me this 20 day of August, 19 62

My commission expires April 8, 1965
Arthur J. Stuebel
Notary Public.



ROTARY DRILLING LOG

FILE COPY

15.135.00099.0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas

LOCATION: McCREIGHT A #1 - C NW NW, Sec. 9-208-24W
Ness County, Kansas

Rotary Drilling Commenced 7/31/61
Rotary Drilling Completed 8/15/61

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

DRAINING RECORD: 283' (6 jts.) 8 5/8" 20# surface casing w/165 sacks cement. Circulated.
4493' (140 jts.) 5 1/2" 14# Smls. Casing cemented w/100 sacks cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>
140'	Surface Clay	4332'
160'	Hard Sand	4385'
300'	Shale & Shells	4400'
405'	Grey Shale Sandy	4410'
765'	Sandy Shale	4416'
825'	Sand, Shale & Red Bed	4421'
960'	Shale & Red Bed	4428'
980'	Red Beds, Shells & Shale	4435'
1000'	Blaine	4440'
1075'	Red Beds	4450'
1325'	Sand	4475'
1575'	Shale & Shells	4494'
1615'	Anhydrite	
2220'	Shale & Shells	
2485'	Lime & Shale	<u>Slope Test</u>
2760'	Lime	1325' 0°
3490'	Lime & Shale	2565' 0°
3566'	Lime & Sand	3490' 0°
3640'	Lime & Shale	4400' 0°
3750'	Lime, Shale & Sand	
3947'	Lime & Shale	<u>S. L. M.</u>
4105'	Lime	1575'
4400'	Lime & Shale	2990'
4494'	Mississippi R.T.D.	3997'

RECEIVED
STATE CORPORATIONS COMMISSION

SEP 19 1962

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 31st day of August, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of each company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
Notary Public