


STATE OF KANSAS
STATE CORPORATION COMMISSION.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 9 Twp. 20 Rge. 24 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C. NW NE
Lease Owner Liberty Enterprises, Inc.
Lease Name McCreight, C#1 Well No. _____
Office Address Plainville, Kansas 67663
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7/18/79 _____ 19____
Plugging completed 7/31/79 _____ 19____
Reason for abandonment of well or producing formation _____
depleted.
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4457'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	320	none
				4 1/2"	4454	3010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 4400' and ran 4 sacks cement. Loaded hole with salt water, shot pipe at 3606',
3405', 3201', 1010', pulled 75 joints. Pumped 2 sacks hulls, 10 sacks gel, 60 sacks cement,
4 sacks gel, 2 sacks hulls, plug and 75 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 79

Margaret Melcher
Notary Public.

My commission expires



D R I L L E R S L O G

#2 McCreight

CASING:
313.97' of used 8-5/8"
surface casing.

COMPANY: R. T. McCreight
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C/NW NE
Section 9-20S-24W
Ness City, Kansas

TOTAL DEPTH:
4434'

COMMENCED: February 6, 1975
COMPLETED: February 15, 1975

D. & A.

FORMATION	FROM	TO	REMARKS
Surface Soil & Clay	0	270	Ran 313.97' of used 8-5/8" surface casing; set and cemented at 320' with 200 sacks of common cement, 2% gel and 3% C. C. Plug down at 2:30 A. M. February 7, 1975.
Surface Soil & Clay	270	335	
Shells, Shale w/Sand Streaks	335	740	
Shale & Red Bed	740	984	
Anhydrite	984	998	
Sand & Red Bed	998	1410	
Red Bed & Shale	1410	1985	
Shale w/Lime	1985	2240	
Shale & Lime	2240	4035	
Lime	4035	4140	
Lime & Shale	4140	4236	
Lime	4236	4255	
Lime & Shale	4255	4434	

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1979

CONSERVATION DIVISION
Wichita, Kansas

ROTARY TOTAL DEPTH: 4434'

Ran electric log.

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Hole plugged as follows: Plugged at 600' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 11:30 A. M. February 15, 1975.


STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 17th day of February, 1975.
My Commission Expires:
December 14, 1977



Elaine H. Taylor
Elaine H. Taylor, Notary Public