


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Kans County, Sec 9 Twp. 20S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines 10E 10E SW
Lease Owner D. R. Lounis Oil Company Inc
Lease Name 1400 ft Well No. 1
Office Address 301 So. Broadway Wichita 2 Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed April 21 19 52
Application for plugging filed April 28 19 52
Application for plugging approved April 30 19 52
Plugging commenced May 9 19 52
Plugging completed May 12 19 52
Reason for abandonment of well or producing formation Formation
produced water only
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Miss. Depth to top _____ Bottom _____ Total Depth of Well 4520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface clay-shells	water			8 5/8	703	none
Mississippi	water	4394	4520	5 1/2	4520	3746

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Water bridge plug
4335
4335 to 4300 sand bridge
4300 to 4205 cement
4205 to 200 mud
200 to 185 rock bridge
185 to 130 cement 10 sack
130 to 30 mud
30 to collar cement 10 sack

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1952
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor _____
Address _____

STATE OF Kansas COUNTY OF sedgwick, ss.
James P. Reinlein (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James P. Reinlein
Wichita Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 52

Sept. 24, 1953

Elizabeth Kay
Notary Public.

PLUGGING
PAGE SEC 9 T 20R 24
BOOK PAGE 17 LINE 31

D.R. Lauck Oil Company, Inc.,
North American Car Corporation.

Commenced Mar. 21, 1952
Completed Apr. 20, 1952

McCreight #1
NE NE SW Sec. 9-20S-24W. Ness County Kansas

Elevation: 2340 DF 2342 KB
8" casing at 193 ft cemented with 125 sacks
5 1/2" casing at 4523 cemented with 100 sacks
9' from spider to K.B.

D & A

surface clay	80
shale & shells	700
sand	720
shale & shells	795
sand	815
shale & shells	1045
shale & sand	1340
red bed	1504
Anhydrite	1605
shale & shells	2204
shale & lime	3610
lime	3640
shale & lime	3725
lime	3855
broken lime	3920
lime	4384
lime & chert	4412
lime	4528

Heebner	3731
Lansing	3810
Congl.	4365
Miss.	4394
T D	4528

DST #1 4371-4412 open 1 hr
rec. 30' mud with slight show oil
OBHP 15"

DST #2 4419-4430 open 1 hr
fair blow rec. 50' oil 15' mud cut oil
60' watery mud 1190# BHP 15 min.

Drilling in:
Perf. 20 shots 4418-22 bail 24 gal. FPW
40% oil 60% water
250 gal. acid; swab 53 BWPH for 3 hrs;
seum oil; static 1650' down;
set Baker plug at 4338 -pl 7' calseal;
Perf. 12 shots 4314-17 no fluid;
500 acid swab 27 BWPH 3 hrs.

RECEIVED
CORPORATION COMMISSION
APR 30 1952
RESERVATION DIVISION
Topeka, Kansas

PLUGGING
FILE SEC 9T20R240
BOOK PAGE 18 LINE 31